



August 5, 2019

Joseph Michael
SB Cera
348 W Hospitality Lane
Suite 108
San Bernardino, CA 92415

SI Testing is pleased to submit the following price information for the following property:

348 W Hospitality San Bernardino

SI Testing will perform the following:

- **Install (1) New Generator Connection Box outside of the building directly opposite the Main Electric Room**
- **Intercept the (2) existing 200amp feeders and extend them to the (2) new 200amp GE Zenith Automatic Transfer Switches**
- **Install (2) new 200amp feeds from the Main Switchgear to the (2) new 200amp GE Zenith Automatic Transfer Switches**
- **Install (2) new emergency feeds from the (2) new 200amp GE Zenith Automatic Transfer Switches to the new temporary generator connection box**
- **Install (2) dedicated circuits for the internet connection that need to be backed up by the generator as well**
- **Verification of voltages and system functionality upon completion of installation**
- **All work will meet NEC Standards**

Total: \$32,029.50

All Testing & Servicing is Done to NETA Specifications and Standards

PLEASE NOTE:

- **Installation is quoted during normal hours**
- **The Cutover is quoted during overtime hours as an isolated outage will be required and there will be no power to the (2) 200amp Breakers for 2-4 hours**
- **Total Price includes material and labor**
- **Estimated lead time on (2) new GE Zenith, 200amp ATS's is 3-4 weeks plus 1 week transit**
- **This proposal is based on the acceptance of the insurance compliance. Compliance for additional insurance requirements may result in additional charges.**

CUSTOMER BILLING INFORMATION
Billing Name:
Billing Address:
Billing City, State, Zip Code
Accounts Payable Contact:
Email:
Phone:
Date:

Exhibit C: Page 2

Sincerely,
SI Testing

David Sincock

ACCEPTED AND AGREED

by: _____ date: _____

SI Testing, C-10 #1015372
9375 Archibald Ave., Suite 403, Rancho Cucamonga, CA 91730 | 877-857-8007